

C & A Consulting Engineers Ltd		Page 0
Landmark House Station Road, Hook Hampshire RG27 9HA	16-010 Sellindge SW DRAINAGE Southern Network lin2YR	
Date 31/01/2022 File 2022 Feb Phase 1A SW Detailed...	Designed by SPS Checked by GAC	
Micro Drainage Network 2019.1		

STORM SEWER DESIGN by the Modified Rational Method

Pipe Sizes STANDARD Manhole Sizes STANDARD

Return Period (years)	2
FEH Rainfall Version	1999
Site Location	GB 611050 137750 TR 11050 37750
C (1km)	-0.023
D1 (1km)	0.346
D2 (1km)	0.375
D3 (1km)	0.302
E (1km)	0.311
F (1km)	2.491
Maximum Rainfall (mm/hr)	50
Maximum Time of Concentration (mins)	30
Foul Sewage (l/s/ha)	0.000
Volumetric Runoff Coeff.	0.750
PIMP (%)	100
Add Flow / Climate Change (%)	0
Minimum Backdrop Height (m)	0.200
Maximum Backdrop Height (m)	0.000
Min Design Depth for Optimisation (m)	1.200
Min Vel for Auto Design only (m/s)	0.75
Min Slope for Optimisation (1:X)	500

Network Design Table for SOUTHERN NETWORK

Network Results Table

C & A Consulting Engineers Ltd

Landmark House
Station Road, Hook
Hampshire RG27 9HA

Date 31/01/2022
File 2022 Feb Phase 1A SW Detailed...

Micro Drainage

16-010 Sellindge
SW DRAINAGE Southern Network
lin2YR

Designed by SPS
Checked by GAC

Network 2019.1

Page 1



Network Design Table for SOUTHERN NETWORK

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
20.011	31.671	0.500	63.3	0.075	0.00	0.0	0.600	o	450	Pipe/Conduit	
~~26.000~~	~~7.804~~	~~1.050~~	~~7.4~~	~~0.028~~	~~5.00~~	~~0.0~~	~~0.600~~	~~o~~	~~150~~	~~Pipe/Conduit~~	~~~~
20.012	30.353	0.540	56.2	0.044	0.00	0.0	0.600	o	450	Pipe/Conduit	
20.013	26.317	0.460	57.2	0.017	0.00	0.0	0.600	oo	450	Double Pipe	
27.000	27.070	0.086	314.8	0.104	5.00	0.0	0.600	o	300	Pipe/Conduit	
27.001	62.149	0.218	285.1	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	
27.002	84.614	0.100	846.1	0.229	0.00	0.0	0.600	\	-1	Pipe/Conduit	
20.014	16.216	0.300	54.1	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	
20.015	69.525	0.500	139.0	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	
20.016	65.090	1.375	47.3	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	
28.000	88.363	0.250	353.5	0.236	5.00	0.0	0.600	o	450	Pipe/Conduit	
28.001	16.417	0.250	65.7	0.000	0.00	0.0	0.600	o	450	Pipe/Conduit	
20.017	56.830	0.050	1136.6	0.000	0.00	0.0	0.600	o	450	Pipe/Conduit	
29.000	14.165	0.450	31.5	0.032	5.00	0.0	0.600	o	225	Pipe/Conduit	
30.000	23.163	0.400	57.9	0.065	5.00	0.0	0.600	o	150	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
20.011	50.00	7.41	65.700	0.729	0.0	0.0	0.0	2.56	406.8	98.7
~~26.000~~	~~50.00~~	~~5.03~~	~~66.550~~	~~0.028~~	~~0.0~~	~~0.0~~	~~0.0~~	~~3.72~~	~~65.7~~	~~3.8~~
20.012	50.00	7.60	65.200	0.801	0.0	0.0	0.0	2.72	432.0	108.5
20.013	50.00	7.76	64.660	0.818	0.0	0.0	0.0	2.69	856.3	110.8
27.000	50.00	5.51	65.300	0.104	0.0	0.0	0.0	0.88	62.3	14.1
27.001	50.00	6.63	65.214	0.104	0.0	0.0	0.0	0.93	65.5	14.1
27.002	50.00	8.14	64.300	0.333	0.0	0.0	0.0	0.94	1497.2	45.1
20.014	50.00	8.29	64.200	1.151	0.0	0.0	0.0	1.78	70.9«	155.9
20.015	50.00	9.34	63.900	1.151	0.0	0.0	0.0	1.11	44.0«	155.9
20.016	50.00	9.91	63.400	1.151	0.0	0.0	0.0	1.91	75.8«	155.9
28.000	50.00	6.37	62.300	0.236	0.0	0.0	0.0	1.08	171.1	32.0
28.001	50.00	6.48	62.050	0.236	0.0	0.0	0.0	2.51	399.5	32.0
20.017	45.30	11.50	61.800	1.387	0.0	0.0	0.0	0.59	94.6«	170.2
29.000	50.00	5.10	64.275	0.032	0.0	0.0	0.0	2.34	93.1	4.3
30.000	50.00	5.29	64.300	0.065	0.0	0.0	0.0	1.32	23.4	8.8

©1982-2019 Innovyze

C & A Consulting Engineers Ltd

Landmark House
Station Road, Hook
Hampshire RG27 9HA

16-010 Sellindge
SW DRAINAGE Southern Network
lin2YR

Date 31/01/2022
File 2022 Feb Phase 1A SW Detailed...

Designed by SPS
Checked by GAC

Micro Drainage

Network 2019.1

Page 2



Network Design Table for SOUTHERN NETWORK

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
29.001	23.906	0.450	53.1	0.036	0.00	0.0	0.600	o	225	Pipe/Conduit	
29.002	18.423	0.400	46.1	0.024	0.00	0.0	0.600	o	225	Pipe/Conduit	
29.003	13.524	0.855	15.8	0.014	0.00	0.0	0.600	o	225	Pipe/Conduit	
31.000	21.643	0.505	42.9	0.036	5.00	0.0	0.600	o	150	Pipe/Conduit	
29.004	10.698	0.037	290.0	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	
32.000	16.342	0.082	200.0	0.063	5.00	0.0	0.600	o	225	Pipe/Conduit	
32.001	17.532	0.088	200.0	0.029	0.00	0.0	0.600	o	225	Pipe/Conduit	
32.002	14.987	0.097	154.5	0.017	0.00	0.0	0.600	o	225	Pipe/Conduit	
29.005	20.932	0.073	286.7	0.000	0.00	0.0	0.600	o	450	Pipe/Conduit	
33.000	17.701	0.220	80.5	0.084	5.00	0.0	0.600	o	225	Pipe/Conduit	
33.001	19.935	0.680	29.3	0.017	0.00	0.0	0.600	o	225	Pipe/Conduit	
33.002	14.941	0.700	21.3	0.013	0.00	0.0	0.600	o	225	Pipe/Conduit	
33.003	53.224	0.763	69.8	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	
34.000	12.850	0.450	28.6	0.071	5.00	0.0	0.600	o	225	Pipe/Conduit	
34.001	41.372	1.438	28.8	0.100	0.00	0.0	0.600	o	225	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
29.001	50.00	5.51	63.825	0.133	0.0	0.0	0.0	1.80	71.5	18.0
29.002	50.00	5.67	63.375	0.157	0.0	0.0	0.0	1.93	76.8	21.3
29.003	50.00	5.74	62.975	0.171	0.0	0.0	0.0	3.31	131.5	23.2
31.000	50.00	5.23	62.700	0.036	0.0	0.0	0.0	1.54	27.2	4.9
29.004	50.00	5.93	62.045	0.207	0.0	0.0	0.0	0.92	64.9	28.0
32.000	50.00	5.30	62.350	0.063	0.0	0.0	0.0	0.92	36.6	8.5
32.001	50.00	5.61	62.268	0.092	0.0	0.0	0.0	0.92	36.6	12.5
32.002	50.00	5.85	62.180	0.109	0.0	0.0	0.0	1.05	41.7	14.8
29.005	50.00	6.23	62.008	0.316	0.0	0.0	0.0	1.20	190.1	42.8
33.000	50.00	5.20	66.375	0.084	0.0	0.0	0.0	1.46	58.0	11.4
33.001	50.00	5.34	66.155	0.101	0.0	0.0	0.0	2.43	96.4	13.7
33.002	50.00	5.43	65.475	0.114	0.0	0.0	0.0	2.84	113.1	15.4
33.003	50.00	5.99	64.775	0.114	0.0	0.0	0.0	1.57	62.3	15.4
34.000	50.00	5.09	66.075	0.071	0.0	0.0	0.0	2.46	97.7	9.6
34.001	50.00	5.37	65.625	0.171	0.0	0.0	0.0	2.45	97.4	23.2

©1982-2019 Innovyze

C & A Consulting Engineers Ltd

Page 3

Landmark House
Station Road, Hook
Hampshire RG27 9HA

16-010 Sellindge
SW DRAINAGE Southern Network
lin2YR

Date 31/01/2022
File 2022 Feb Phase 1A SW Detailed...

Designed by SPS
Checked by GAC

Micro Drainage

Network 2019.1

Network Design Table for SOUTHERN NETWORK

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
35.000	18.492	0.800	23.1	0.038	5.00	0.0	0.600	o	150	Pipe/Conduit	
35.001	27.799	0.350	79.4	0.041	0.00	0.0	0.600	o	225	Pipe/Conduit	
35.002	6.867	0.088	78.0	0.011	0.00	0.0	0.600	o	225	Pipe/Conduit	
34.002	5.260	0.175	30.1	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	
33.004	126.153	1.862	67.8	0.000	0.00	0.0	0.600	o	450	Pipe/Conduit	
29.006	34.833	0.135	258.0	0.000	0.00	0.0	0.600	o	450	Pipe/Conduit	
20.018	6.018	0.125	48.1	0.000	0.00	0.0	0.600	\/	-1	Pipe/Conduit	
20.019	14.451	0.194	74.5	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
35.000	50.00	5.15	65.500	0.038	0.0	0.0	0.0	2.10	37.2	5.1
35.001	50.00	5.46	64.625	0.079	0.0	0.0	0.0	1.47	58.4	10.7
35.002	50.00	5.54	64.275	0.090	0.0	0.0	0.0	1.48	58.9	12.2
34.002	50.00	5.58	64.187	0.261	0.0	0.0	0.0	2.40	95.2	35.3
33.004	50.00	6.84	63.787	0.375	0.0	0.0	0.0	2.47	393.3	50.8
29.006	50.00	7.30	61.935	0.691	0.0	0.0	0.0	1.26	200.5	93.6
20.018	45.24	11.52	61.750	2.078	0.0	0.0	0.0	3.96	6340.6	254.6
20.019	44.82	11.68	61.625	2.078	0.0	0.0	0.0	1.52	60.3«	254.6

Free Flowing Outfall Details for SOUTHERN NETWORK

Outfall Pipe Number	Outfall Name	C. Level (m)	I. Level (m)	Min I. Level (m)	D,I (mm)	W (mm)
20.019	Outfall 03	62.200	61.431	60.400	0	0

Simulation Criteria for SOUTHERN NETWORK

Volumetric Runoff Coeff	0.750	Additional Flow - % of Total Flow	0.000
Areal Reduction Factor	1.000	MADD Factor * 10m³/ha Storage	2.000
Hot Start (mins)	0	Inlet Coefficient	0.800
Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000
Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60
Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1
Number of Input Hydrographs	0	Number of Storage Structures	7
Number of Online Controls	5	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

©1982-2019 Innovyze

C & A Consulting Engineers Ltd		Page 5																																																																								
Landmark House Station Road, Hook Hampshire RG27 9HA	16-010 Sellindge SW DRAINAGE Southern Network 1in2YR																																																																									
Date 31/01/2022	Designed by SPS																																																																									
File 2022 Feb Phase 1A SW Detailed...	Checked by GAC																																																																									
Micro Drainage	Network 2019.1																																																																									
<u>Online Controls for SOUTHERN NETWORK</u>																																																																										
<u>Orifice Manhole: 115, DS/PN: 20.008, Volume (m³): 4.4</u>																																																																										
Diameter (m) 0.340 Discharge Coefficient 0.600 Invert Level (m) 67.300																																																																										
<u>Hydro-Brake® Optimum Manhole: 127, DS/PN: 20.014, Volume (m³): 142.6</u>																																																																										
Unit Reference MD-SFP-0152-1200-1000-1200																																																																										
Design Head (m) 1.000																																																																										
Design Flow (l/s) 12.0																																																																										
Flush-Flo™ Calculated																																																																										
Objective Future Proof																																																																										
Application Surface																																																																										
Sump Available Yes																																																																										
Diameter (mm) 152																																																																										
Invert Level (m) 64.200																																																																										
Minimum Outlet Pipe Diameter (mm) 225																																																																										
Suggested Manhole Diameter (mm) 1200																																																																										
<table><tr><td>Control Points</td><td>Head (m)</td><td>Flow (l/s)</td></tr><tr><td>Design Point (Calculated)</td><td>1.000</td><td>12.0</td></tr><tr><td>Flush-Flo™</td><td>0.264</td><td>12.0</td></tr><tr><td>Kick-Flo®</td><td>0.635</td><td>9.7</td></tr><tr><td>Mean Flow over Head Range</td><td>-</td><td>10.1</td></tr></table>			Control Points	Head (m)	Flow (l/s)	Design Point (Calculated)	1.000	12.0	Flush-Flo™	0.264	12.0	Kick-Flo®	0.635	9.7	Mean Flow over Head Range	-	10.1																																																									
Control Points	Head (m)	Flow (l/s)																																																																								
Design Point (Calculated)	1.000	12.0																																																																								
Flush-Flo™	0.264	12.0																																																																								
Kick-Flo®	0.635	9.7																																																																								
Mean Flow over Head Range	-	10.1																																																																								
The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated																																																																										
<table><tr><td>Depth (m)</td><td>Flow (l/s)</td><td>Depth (m)</td><td>Flow (l/s)</td><td>Depth (m)</td><td>Flow (l/s)</td><td>Depth (m)</td><td>Flow (l/s)</td></tr><tr><td>0.100</td><td>5.8</td><td>1.200</td><td>13.1</td><td>3.000</td><td>20.2</td><td>7.000</td><td>30.3</td></tr><tr><td>0.200</td><td>11.8</td><td>1.400</td><td>14.1</td><td>3.500</td><td>21.7</td><td>7.500</td><td>31.4</td></tr><tr><td>0.300</td><td>12.0</td><td>1.600</td><td>15.0</td><td>4.000</td><td>23.2</td><td>8.000</td><td>32.3</td></tr><tr><td>0.400</td><td>11.6</td><td>1.800</td><td>15.8</td><td>4.500</td><td>24.5</td><td>8.500</td><td>33.3</td></tr><tr><td>0.500</td><td>11.2</td><td>2.000</td><td>16.6</td><td>5.000</td><td>25.8</td><td>9.000</td><td>34.2</td></tr><tr><td>0.600</td><td>10.3</td><td>2.200</td><td>17.4</td><td>5.500</td><td>27.0</td><td>9.500</td><td>35.1</td></tr><tr><td>0.800</td><td>10.8</td><td>2.400</td><td>18.2</td><td>6.000</td><td>28.2</td><td></td><td></td></tr><tr><td>1.000</td><td>12.0</td><td>2.600</td><td>18.9</td><td>6.500</td><td>29.3</td><td></td><td></td></tr></table>			Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	0.100	5.8	1.200	13.1	3.000	20.2	7.000	30.3	0.200	11.8	1.400	14.1	3.500	21.7	7.500	31.4	0.300	12.0	1.600	15.0	4.000	23.2	8.000	32.3	0.400	11.6	1.800	15.8	4.500	24.5	8.500	33.3	0.500	11.2	2.000	16.6	5.000	25.8	9.000	34.2	0.600	10.3	2.200	17.4	5.500	27.0	9.500	35.1	0.800	10.8	2.400	18.2	6.000	28.2			1.000	12.0	2.600	18.9	6.500	29.3		
Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)																																																																			
0.100	5.8	1.200	13.1	3.000	20.2	7.000	30.3																																																																			
0.200	11.8	1.400	14.1	3.500	21.7	7.500	31.4																																																																			
0.300	12.0	1.600	15.0	4.000	23.2	8.000	32.3																																																																			
0.400	11.6	1.800	15.8	4.500	24.5	8.500	33.3																																																																			
0.500	11.2	2.000	16.6	5.000	25.8	9.000	34.2																																																																			
0.600	10.3	2.200	17.4	5.500	27.0	9.500	35.1																																																																			
0.800	10.8	2.400	18.2	6.000	28.2																																																																					
1.000	12.0	2.600	18.9	6.500	29.3																																																																					
<u>Hydro-Brake® Optimum Manhole: 156, DS/PN: 20.018, Volume (m³): 16.3</u>																																																																										
Unit Reference MD-SHE-0199-2090-1250-2090																																																																										
Design Head (m) 1.250																																																																										
Design Flow (l/s) 20.9																																																																										
Flush-Flo™ Calculated																																																																										
Objective Minimise upstream storage																																																																										
Application Surface																																																																										
Sump Available Yes																																																																										
Diameter (mm) 199																																																																										
Invert Level (m) 61.750																																																																										
Minimum Outlet Pipe Diameter (mm) 225																																																																										
Suggested Manhole Diameter (mm) 1500																																																																										
©1982-2019 Innovyze																																																																										

C & A Consulting Engineers Ltd			Page 6																																																																								
Landmark House Station Road, Hook Hampshire RG27 9HA	16-010 Sellindge SW DRAINAGE Southern Network 1in2YR																																																																										
Date 31/01/2022	Designed by SPS																																																																										
File 2022 Feb Phase 1A SW Detailed...	Checked by GAC																																																																										
Micro Drainage	Network 2019.1																																																																										
<u>Hydro-Brake® Optimum Manhole: 156, DS/PN: 20.018, Volume (m³): 16.3</u>																																																																											
<table><thead><tr><th>Control Points</th><th>Head (m)</th><th>Flow (l/s)</th></tr></thead><tbody><tr><td>Design Point (Calculated)</td><td>1.250</td><td>20.9</td></tr><tr><td>Flush-Flo™</td><td>0.393</td><td>20.8</td></tr><tr><td>Kick-Flo®</td><td>0.858</td><td>17.5</td></tr><tr><td>Mean Flow over Head Range</td><td>-</td><td>17.8</td></tr></tbody></table>				Control Points	Head (m)	Flow (l/s)	Design Point (Calculated)	1.250	20.9	Flush-Flo™	0.393	20.8	Kick-Flo®	0.858	17.5	Mean Flow over Head Range	-	17.8																																																									
Control Points	Head (m)	Flow (l/s)																																																																									
Design Point (Calculated)	1.250	20.9																																																																									
Flush-Flo™	0.393	20.8																																																																									
Kick-Flo®	0.858	17.5																																																																									
Mean Flow over Head Range	-	17.8																																																																									
The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated																																																																											
<table><thead><tr><th>Depth (m)</th><th>Flow (l/s)</th><th>Depth (m)</th><th>Flow (l/s)</th><th>Depth (m)</th><th>Flow (l/s)</th><th>Depth (m)</th><th>Flow (l/s)</th></tr></thead><tbody><tr><td>0.100</td><td>6.9</td><td>1.200</td><td>20.5</td><td>3.000</td><td>31.8</td><td>7.000</td><td>47.8</td></tr><tr><td>0.200</td><td>18.8</td><td>1.400</td><td>22.0</td><td>3.500</td><td>34.2</td><td>7.500</td><td>49.4</td></tr><tr><td>0.300</td><td>20.6</td><td>1.600</td><td>23.5</td><td>4.000</td><td>36.5</td><td>8.000</td><td>51.0</td></tr><tr><td>0.400</td><td>20.8</td><td>1.800</td><td>24.9</td><td>4.500</td><td>38.6</td><td>8.500</td><td>52.5</td></tr><tr><td>0.500</td><td>20.6</td><td>2.000</td><td>26.1</td><td>5.000</td><td>40.6</td><td>9.000</td><td>54.0</td></tr><tr><td>0.600</td><td>20.3</td><td>2.200</td><td>27.4</td><td>5.500</td><td>42.5</td><td>9.500</td><td>55.5</td></tr><tr><td>0.800</td><td>18.6</td><td>2.400</td><td>28.5</td><td>6.000</td><td>44.4</td><td></td><td></td></tr><tr><td>1.000</td><td>18.8</td><td>2.600</td><td>29.7</td><td>6.500</td><td>46.1</td><td></td><td></td></tr></tbody></table>				Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	0.100	6.9	1.200	20.5	3.000	31.8	7.000	47.8	0.200	18.8	1.400	22.0	3.500	34.2	7.500	49.4	0.300	20.6	1.600	23.5	4.000	36.5	8.000	51.0	0.400	20.8	1.800	24.9	4.500	38.6	8.500	52.5	0.500	20.6	2.000	26.1	5.000	40.6	9.000	54.0	0.600	20.3	2.200	27.4	5.500	42.5	9.500	55.5	0.800	18.6	2.400	28.5	6.000	44.4			1.000	18.8	2.600	29.7	6.500	46.1		
Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)																																																																				
0.100	6.9	1.200	20.5	3.000	31.8	7.000	47.8																																																																				
0.200	18.8	1.400	22.0	3.500	34.2	7.500	49.4																																																																				
0.300	20.6	1.600	23.5	4.000	36.5	8.000	51.0																																																																				
0.400	20.8	1.800	24.9	4.500	38.6	8.500	52.5																																																																				
0.500	20.6	2.000	26.1	5.000	40.6	9.000	54.0																																																																				
0.600	20.3	2.200	27.4	5.500	42.5	9.500	55.5																																																																				
0.800	18.6	2.400	28.5	6.000	44.4																																																																						
1.000	18.8	2.600	29.7	6.500	46.1																																																																						
©1982-2019 Innovyze																																																																											

C & A Consulting Engineers Ltd		Page 7																																																																																																																																				
Landmark House Station Road, Hook Hampshire RG27 9HA	16-010 Sellindge SW DRAINAGE Southern Network lin2YR																																																																																																																																					
Date 31/01/2022	Designed by SPS																																																																																																																																					
File 2022 Feb Phase 1A SW Detailed...	Checked by GAC																																																																																																																																					
Micro Drainage	Network 2019.1																																																																																																																																					
<u>Storage Structures for SOUTHERN NETWORK</u> <u>Porous Car Park Manhole: 123, DS/PN: 20.013</u> <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.00000</td><td>Width (m)</td><td>8.6</td></tr><tr><td>Membrane Percolation (mm/hr)</td><td>1000</td><td>Length (m)</td><td>29.0</td></tr><tr><td>Max Percolation (l/s)</td><td>69.3</td><td>Slope (1:X)</td><td>500.0</td></tr><tr><td>Safety Factor</td><td>2.0</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Porosity</td><td>0.30</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Invert Level (m)</td><td>66.200</td><td>Membrane Depth (mm)</td><td>0</td></tr></table> <u>Tank or Pond Manhole: 127, DS/PN: 20.014</u> Invert Level (m) 64.200 <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th></tr><tr><td>0.000</td><td>625.0</td><td>0.500</td><td>976.0</td><td>1.000</td><td>1351.0</td></tr><tr><td>0.250</td><td>798.0</td><td>0.750</td><td>1160.0</td><td></td><td></td></tr></table> <u>Porous Car Park Manhole: 136, DS/PN: 29.001</u> <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.00000</td><td>Width (m)</td><td>15.7</td></tr><tr><td>Membrane Percolation (mm/hr)</td><td>1000</td><td>Length (m)</td><td>20.7</td></tr><tr><td>Max Percolation (l/s)</td><td>90.3</td><td>Slope (1:X)</td><td>500.0</td></tr><tr><td>Safety Factor</td><td>2.0</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Porosity</td><td>0.30</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Invert Level (m)</td><td>63.825</td><td>Membrane Depth (mm)</td><td>0</td></tr></table> <u>Porous Car Park Manhole: 143, DS/PN: 29.004</u> <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.00000</td><td>Width (m)</td><td>10.7</td></tr><tr><td>Membrane Percolation (mm/hr)</td><td>1000</td><td>Length (m)</td><td>18.6</td></tr><tr><td>Max Percolation (l/s)</td><td>55.3</td><td>Slope (1:X)</td><td>500.0</td></tr><tr><td>Safety Factor</td><td>2.0</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Porosity</td><td>0.30</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Invert Level (m)</td><td>63.500</td><td>Membrane Depth (mm)</td><td>0</td></tr></table> <u>Porous Car Park Manhole: 151, DS/PN: 35.001</u> <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.00000</td><td>Width (m)</td><td>13.0</td></tr><tr><td>Membrane Percolation (mm/hr)</td><td>1000</td><td>Length (m)</td><td>13.7</td></tr><tr><td>Max Percolation (l/s)</td><td>49.5</td><td>Slope (1:X)</td><td>500.0</td></tr><tr><td>Safety Factor</td><td>2.0</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Porosity</td><td>0.30</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Invert Level (m)</td><td>65.350</td><td>Membrane Depth (mm)</td><td>0</td></tr></table> <u>Tank or Pond Manhole: 156, DS/PN: 20.018</u> Invert Level (m) 61.750 <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th></tr><tr><td>0.000</td><td>159.0</td><td>0.500</td><td>400.0</td><td>1.000</td><td>670.0</td></tr><tr><td>0.250</td><td>274.0</td><td>0.750</td><td>532.0</td><td>1.250</td><td>814.0</td></tr></table>			Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	8.6	Membrane Percolation (mm/hr)	1000	Length (m)	29.0	Max Percolation (l/s)	69.3	Slope (1:X)	500.0	Safety Factor	2.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	66.200	Membrane Depth (mm)	0	Depth (m)	Area (m²)	Depth (m)	Area (m²)	Depth (m)	Area (m²)	0.000	625.0	0.500	976.0	1.000	1351.0	0.250	798.0	0.750	1160.0			Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	15.7	Membrane Percolation (mm/hr)	1000	Length (m)	20.7	Max Percolation (l/s)	90.3	Slope (1:X)	500.0	Safety Factor	2.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	63.825	Membrane Depth (mm)	0	Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	10.7	Membrane Percolation (mm/hr)	1000	Length (m)	18.6	Max Percolation (l/s)	55.3	Slope (1:X)	500.0	Safety Factor	2.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	63.500	Membrane Depth (mm)	0	Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	13.0	Membrane Percolation (mm/hr)	1000	Length (m)	13.7	Max Percolation (l/s)	49.5	Slope (1:X)	500.0	Safety Factor	2.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	65.350	Membrane Depth (mm)	0	Depth (m)	Area (m²)	Depth (m)	Area (m²)	Depth (m)	Area (m²)	0.000	159.0	0.500	400.0	1.000	670.0	0.250	274.0	0.750	532.0	1.250	814.0
Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	8.6																																																																																																																																			
Membrane Percolation (mm/hr)	1000	Length (m)	29.0																																																																																																																																			
Max Percolation (l/s)	69.3	Slope (1:X)	500.0																																																																																																																																			
Safety Factor	2.0	Depression Storage (mm)	5																																																																																																																																			
Porosity	0.30	Evaporation (mm/day)	3																																																																																																																																			
Invert Level (m)	66.200	Membrane Depth (mm)	0																																																																																																																																			
Depth (m)	Area (m²)	Depth (m)	Area (m²)	Depth (m)	Area (m²)																																																																																																																																	
0.000	625.0	0.500	976.0	1.000	1351.0																																																																																																																																	
0.250	798.0	0.750	1160.0																																																																																																																																			
Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	15.7																																																																																																																																			
Membrane Percolation (mm/hr)	1000	Length (m)	20.7																																																																																																																																			
Max Percolation (l/s)	90.3	Slope (1:X)	500.0																																																																																																																																			
Safety Factor	2.0	Depression Storage (mm)	5																																																																																																																																			
Porosity	0.30	Evaporation (mm/day)	3																																																																																																																																			
Invert Level (m)	63.825	Membrane Depth (mm)	0																																																																																																																																			
Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	10.7																																																																																																																																			
Membrane Percolation (mm/hr)	1000	Length (m)	18.6																																																																																																																																			
Max Percolation (l/s)	55.3	Slope (1:X)	500.0																																																																																																																																			
Safety Factor	2.0	Depression Storage (mm)	5																																																																																																																																			
Porosity	0.30	Evaporation (mm/day)	3																																																																																																																																			
Invert Level (m)	63.500	Membrane Depth (mm)	0																																																																																																																																			
Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	13.0																																																																																																																																			
Membrane Percolation (mm/hr)	1000	Length (m)	13.7																																																																																																																																			
Max Percolation (l/s)	49.5	Slope (1:X)	500.0																																																																																																																																			
Safety Factor	2.0	Depression Storage (mm)	5																																																																																																																																			
Porosity	0.30	Evaporation (mm/day)	3																																																																																																																																			
Invert Level (m)	65.350	Membrane Depth (mm)	0																																																																																																																																			
Depth (m)	Area (m²)	Depth (m)	Area (m²)	Depth (m)	Area (m²)																																																																																																																																	
0.000	159.0	0.500	400.0	1.000	670.0																																																																																																																																	
0.250	274.0	0.750	532.0	1.250	814.0																																																																																																																																	
©1982-2019 Innovyze																																																																																																																																						

C & A Consulting Engineers Ltd		Page 8
Landmark House Station Road, Hook Hampshire RG27 9HA	16-010 Sellindge SW DRAINAGE Southern Network lin2YR	
Date 31/01/2022 File 2022 Feb Phase 1A SW Detailed...	Designed by SPS Checked by GAC	
Micro Drainage Network 2019.1		

Summary of Critical Results by Maximum Level (Rank 1) for SOUTHERN NETWORK

Simulation Criteria

Areal Reduction Factor 1.000	Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0	MADD Factor * 10m ³ /ha Storage 2.000
Hot Start Level (mm) 0	Inlet Coefficient 0.800
Manhole Headloss Coeff (Global) 0.500	Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000	

Number of Input Hydrographs 0	Number of Storage Structures 7
Number of Online Controls 5	Number of Time/Area Diagrams 0
Number of Offline Controls 0	Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model	FEH
FEH Rainfall Version	1999
Site Location GB 611050 137750 TR 11050 37750	
C (1km)	-0.023
D1 (1km)	0.346
D2 (1km)	0.375
D3 (1km)	0.302
E (1km)	0.311
F (1km)	2.491
Cv (Summer)	0.750
Cv (Winter)	0.840

Margin for Flood Risk Warning (mm)	300.0
Analysis Timestep 2.5 Second Increment (Extended)	
DTS Status	ON
DVD Status	OFF
Inertia Status	OFF

Profile(s)	Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 240, 360, 480, 960, 1440	
Return Period(s) (years)	2
Climate Change (%)	0

	US/MH	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
20.008	115	15 Winter	2	+0%					67.618
20.009	116	15 Winter	2	+0%					66.768
25.000	117	15 Winter	2	+0%					66.135
20.010	118	15 Winter	2	+0%					66.033
20.011	119	15 Winter	2	+0%					65.864
~~26.000~~	~~121~~	~~15 Winter~~	~~2~~	~~+0%~~					~~66.579~~
20.012	122	15 Winter	2	+0%					65.367
20.013	123	15 Winter	2	+0%					64.772
27.000	124	15 Winter	2	+0%					65.416
27.001	125	15 Winter	2	+0%					65.321
27.002	126	360 Winter	2	+0%					64.372
20.014	127	360 Winter	2	+0%					64.372
20.015	128	360 Winter	2	+0%					63.978
20.016	130	360 Winter	2	+0%					63.459

Landmark House
Station Road, Hook
Hampshire RG27 9HA

16-010 Sellindge SW DRAINAGE Southern Network 1in2YR
--

Date 31/01/2022

Designed by SPS

File 2022 Feb Phase 1A SW Detailed...

Checked by GAC

Micro Drainage

Network 2019.1



Summary of Critical Results by Maximum Level (Rank 1) for SOUTHERN NETWORK

PN	US/MH Name	Surcharged	Flooded	Flow / Cap.	Overflow (l/s)	Pipe	Status	Level Exceeded
		Depth (m)	Volume (m³)			Flow (l/s)		
20.008	115	-0.132	0.000	0.16		71.5	OK	
20.009	116	-0.332	0.000	0.15		79.9	OK	
25.000	117	-0.165	0.000	0.16		4.7	OK	
20.010	118	-0.217	0.000	0.53		90.9	OK	
20.011	119	-0.286	0.000	0.28		99.9	OK	
~~26.000~~	~~121~~	~~-0.121~~	~~0.000~~	~~0.08~~		~~4.8~~	~~OK~~	
20.012	122	-0.283	0.000	0.29		108.9	OK	
20.013	123	-0.338	0.000	0.15		109.2	OK	
27.000	124	-0.184	0.000	0.31		17.4	OK	
27.001	125	-0.193	0.000	0.28		17.3	OK	
27.002	126	-0.328	0.000	0.01		8.8	OK	
20.014	127	-0.053	0.000	0.18		11.3	OK	
20.015	128	-0.147	0.000	0.26		11.3	OK	
20.016	130	-0.166	0.000	0.15		11.3	OK	

C & A Consulting Engineers Ltd								Page 10	
Landmark House Station Road, Hook Hampshire RG27 9HA					16-010 Sellindge SW DRAINAGE Southern Network lin2YR				
Date 31/01/2022					Designed by SPS				
File 2022 Feb Phase 1A SW Detailed...					Checked by GAC				
Micro Drainage					Network 2019.1				
<u>Summary of Critical Results by Maximum Level (Rank 1) for SOUTHERN NETWORK</u>									

Landmark House
Station Road, Hook
Hampshire RG27 9HA

16-010 Sellindge SW DRAINAGE Southern Network 1in2YR
--

Date 31/01/2022

Designed by SPS

File 2022 Feb Phase 1A SW Detailed...

Checked by GAC



Micro Drainage

Network 2019.1

Summary of Critical Results by Maximum Level (Rank 1) for SOUTHERN NETWORK

PN	US/MH	Surcharged	Flooded			Pipe	Status	Level Exceeded
	Name	Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Flow (l/s)		
33.003	147	-0.139	0.000	0.31		18.6	OK	
34.000	148	-0.168	0.000	0.14		12.1	OK	
34.001	149	-0.143	0.000	0.28		26.3	OK	
35.000	150	-0.106	0.000	0.19		6.5	OK	
35.001	151	-0.152	0.000	0.23		12.3	OK	
35.002	152	-0.135	0.000	0.33		14.0	OK	
34.002	153	-0.087	0.000	0.69		40.5	OK	
33.004	154	-0.332	0.000	0.15		57.0	OK	
29.006	155	-0.220	0.000	0.51		90.0	OK	
20.018	156	-0.066	0.000	0.01		20.7	OK	
20.019	157	-0.127	0.000	0.39		20.7	OK	