

× 1.915m

× 1.200m

× 1.897m

× 1.200m

1.200m

FOR CONTINUATION SEE SHEET NUMBER 010

× 1.885m

× 1.907m

SHALLOW DITCH
FROM HEADWALL


4

© This drawing and its content are the copyright of SLR Consulting Ltd and may not be reproduced or amended except by prior written permission. SLR Consulting Ltd accepts no liability for any amendments made by other persons

1. SURVEY CARRIED OUT BY SLR CONSULTING LTD 28-30th MAY 2019.
2. TOPOGRAPHICAL SURVEY INFORMATION SHOWN ON THIS DRAWING IS BASED UPON THE ORDINANCE SURVEY NATIONAL GRID HEATH AND PLAIN DATUM DERIVED BY G.P.S. (OSNTN/OSGB83).
3. THE ACCURACY OF THIS SURVEY IS COMMENSURATE WITH THE DRAWING SCALE SPECIFIED WITHIN THE TITLE BLOCK. CHECK ALL CRUCIAL DIMENSIONS ON-SITE.
4. SERVICES INCLUDING MANHOLES AND TELEGRAPH POSTS HAVE BEEN SURVEYED WHERE FOUND.
5. WHILST EVERY EFFORT HAS BEEN MADE TO INCLUDE ALL ACCESSIBLE DETAILS, FEATURES MAY NOT BE SHOWN IF OBSCURED AT THE TIME OF SURVEY (e.g. AREA OVERGROWN/TOPCKLIES).
6. PREVIOUS SURVEY INFORMATION SHOWN IN GREY TAKEN FROM DRAWING REFERENCE *Topographical Survey Fishing Pond* (AS SUPPLIED BY SHEPNESS RECYCLING (HYTHY) LTD

	PROPOSED MAJOR CONTOURS AT 500mm INTERVALS
	PROPOSED MINOR CONTOURS AT 100mm INTERVALS
	INDICATIVE VEHICLE ROUTE
	PERMANENT WATER
	PROPOSED HEADWALL

2	PS	IMR	3/24	GENERAL UPDATE
1	PS	IMR	2/24	GENERAL UPDATE
0	PS	IMR	7/23	PRELIMINARY ISSUE
Revision	By	Chk'd By	Date	Comments
				
  global environmental solutions				
Site MARTELLO LAKES, HYTHE, KENT				
Project NICKHOLLS QUARRY REDEVELOPMENT				
Drawing Title PROPOSED LAYOUT NORTHERN POND				
Scale 1:100 @ A1			Date JUNE 2023	
Drawing Number 011				Revision 2



NOTES

1. SURVEY CARRIED OUT BY SLR CONSULTING LTD 28-30th MAY 2019.

2. TOPOGRAPHICAL SURVEY INFORMATION SHOWN ON THIS DRAWING IS BASED UPON THE ORDNANCE SURVEY NATIONAL GRID HEIGHT AND PLAN DATUM DERIVED BY G.P.S (OSTN15, OSG83).

3. THE ACCURACY OF THIS SURVEY IS COMMENSURATE WITH THE DRAWING SCALE SPECIFIED WITHIN THE TITLE BLOCK. CHECK ALL CRUCIAL DIMENSIONS ON-SITE.

4. SERVICES INCLUDING MANHOLES AND TELEGRAPH POSTS HAVE BEEN SURVEYED WHERE FOUND.

5. WHILST EVERY EFFORT HAS BEEN MADE TO INCLUDE ALL ACCESSIBLE DETAIL, SOME FEATURES MAY NOT BE SHOWN IF OBSCURED AT THE TIME OF SURVEY (e.g. AREA OVERGROWN/STOCKPILES)


6. PREVIOUS SURVEY INFORMATION SHOWN IN GREY TAKEN FROM DRAWING REFERENCE *Topographical Survey Fishing Swims.dwg* SUPPLIED BY SHEERNESS RECYCLING (HYTHE) LTD

- LEGEND
- PROPOSED MAJOR CONTOURS AT 500mm INTERVALS
 - PROPOSED MINOR CONTOURS AT 100mm INTERVALS
 - INDICATIVE VEHICLE ROUTE
 - PERMANENT WATER


2	PS	IMR	3/24	GENERAL UPDATE.
1	PS	IMR	2/24	GENERAL UPDATE.
0	PS	IMR	7/23	PRELIMINARY ISSUE.
Revision	By	Chk'd By	Date	Comments
SHEERNESS RECYCLING LTD				
SLR global environmental solutions				
Site: MARTELLO LAKES, HYTHE, KENT				
Project: NICKHOLLS QUARRY REDEVELOPMENT				
Drawing Title: PROPOSED LAYOUT NORTHERN OUTLET DETAIL SHEET 5				
Scale: 1:100 @ A1			Date: JUNE 2023	
Drawing Number: 012			Revision: 2	

425.10388.00001-Hythe_development_brown_MASTER 26.03.2024.DWG


425.10084.0000-1497ms - development1 (new).MASTER:26.03.2024.DWG




SECTION 1 - 1 SOUTHERN POND & ACCESS ROAD




SECTION 2 - 2 THROUGH ACCESS RAMP




SECTION 3 - 3 CULVERTS AT BRIDGE LINK




SECTION 4 - 4 HEADWALL NORTH POND



SECTION 5 - 5 AT OUTFALL TO LAKE



SECTION 6 - 6 NORTH ROAD CULVERT




SECTION 7 - 7 SUBSTATION TO REED BED

- NOTES
1. SURVEY CARRIED OUT BY SLR CONSULTING LTD 28-30th MAY 2019.
 2. TOPOGRAPHICAL SURVEY INFORMATION SHOWN ON THIS DRAWING IS BASED UPON THE ORDNANCE SURVEY NATIONAL GRID HEIGHT AND PLAN DATUM DERIVED BY G.P.S. (OSTN15.09GB36).
 3. THE ACCURACY OF THIS SURVEY IS COMMENSURATE WITH THE DRAWING SCALE SPECIFIED WITHIN THE TITLE BLOCK. CHECK ALL CRUCIAL DIMENSIONS ON-SITE.
 4. SERVICES INCLUDING MANHOLES AND TELEGRAPH POSTS HAVE BEEN SURVEYED WHERE FOUND.
 5. WHILST EVERY EFFORT HAS BEEN MADE TO INCLUDE ALL ACCESSIBLE DETAIL, SOME FEATURES MAY NOT BE SHOWN IF OBSCURED AT THE TIME OF SURVEY (e.g. AREA OVERGROWN/STOCKPILES).
 6. PREVIOUS SURVEY INFORMATION SHOWN IN GREY TAKEN FROM DRAWING REFERENCE Topographical Survey Fishing Swims.dwg SUPPLIED BY SHEERNESS RECYCLING (HYTHE) LTD


- LEGEND
- EXISTING GROUND PROFILE
 - PROPOSED GROUND PROFILE

2	PS	IMR	3/24	GENERAL UPDATE.
1	PS	IMR	2/24	GENERAL UPDATE.
0	PS	IMR	7/23	FIRST ISSUE.
Revision	By	Chkd By	Date	Comments
SHEERNESS RECYCLING LTD				
SLR global environmental solutions				
Site: MARTELLO LAKES, HYTHE, KENT				
Project: NICKHOLLS QUARRY REDEVELOPMENT				
Drawing Title: PROPOSED LAYOUT DETAIL SECTIONS				
Scale: 1:500 @ A1			Date: AUGUST 2021	
Drawing Number: 013			Revision: 2	


L:\S:\M&E\150001\Drawings\MASTER 3.0\0206.dwg




SECTION THROUGH OUTFALL (CATCHMENT A)
1:50




SECTION THROUGH OUTFALL (CATCHMENT B)
1:50



SECTION THROUGH OUTFALL (CATCHMENT C)
1:50



LATERAL WEIR
(LONG SECTION)
1:50




LATERAL WEIR
(CROSS SECTION)
1:50

- NOTES
1. SURVEY CARRIED OUT BY SLR CONSULTING LTD 28-30th MAY 2019.
 2. TOPOGRAPHICAL SURVEY INFORMATION SHOWN ON THIS DRAWING IS BASED UPON THE ORDNANCE SURVEY NATIONAL GRID HEIGHT AND PLAN DATUM DERIVED BY G.P.S. (OSTN15 OSGB36).
 3. THE ACCURACY OF THIS SURVEY IS COMMENSURATE WITH THE DRAWING SCALE SPECIFIED WITHIN THE TITLE BLOCK. CHECK ALL CRUCIAL DIMENSIONS ON-SITE.
 4. SERVICES INCLUDING MANHOLES AND TELEGRAPH POSTS HAVE BEEN SURVEYED WHERE FOUND.
 5. WHILST EVERY EFFORT HAS BEEN MADE TO INCLUDE ALL ACCESSIBLE DETAIL, SOME FEATURES MAY NOT BE SHOWN IF OBSOURED AT THE TIME OF SURVEY (e.g. AREA OVERGROWN/STOCKPILES).
 6. PREVIOUS SURVEY INFORMATION SHOWN IN GREY TAKEN FROM DRAWING REFERENCE Topographical Survey Fishing Swims.dwg SUPPLIED BY SHEERNESS RECYCLING (HYTHE) LTD.


LEGEND

1	PS	IMR	2/24	GENERAL UPDATE.
0	DH	IMR	7/23	FIRST ISSUE.
Revision	By	Chkd By	Date	Comments
SHEERNESS RECYCLING LTD				
SLR global environmental solutions				
Site: MARTELLO LAKES, HYTHE, KENT				
Project: NICKHOLLS QUARRY REDEVELOPMENT				
Drawing Title: PROPOSED CONSTRUCTION DETAILS (SHEET 1 OF 2)				
Scale: 1:50 @ A1			Date: JULY 2023	
Drawing Number: 014			Revision: 1	



LEGEND	
--------	--


2	IMR	DW	3/24	300mm Culvert detail added.
1	PS	IMR	2/24	GENERAL UPDATE.
0	DH	IMR	7/23	FIRST ISSUE.
Revision	By	Chk'd By	Date	Comments
SHEE R NESS RECYCLING LTD				
		GREENWOOD HOUSE ROWDEN LANE BRADFORD-ON-AVON WILTS. BA15 2AU T: 01225 309400 F: 01225 309401 www.stroonmilling.com		
global environmental solutions				
Site MARTELO LAKES, HYTHE, KENT				
Project NICKHOLLS QUARRY REDEVELOPMENT				
Drawing Title PROPOSED CONSTRUCTION DETAILS (SHEET 2 OF 2)				
Scale 1:50 @ A1		Date JULY 2023		
Drawing Number 015				Revision 2



- NOTES
1. SURVEY CARRIED OUT BY SLR CONSULTING LTD 28-30th MAY 2019.
 2. TOPOGRAPHICAL SURVEY INFORMATION SHOWN ON THIS DRAWING IS BASED UPON THE ORDNANCE SURVEY NATIONAL GRID HEIGHT AND PLAN DATUM DERIVED BY G.P.S. (OSTN15, OSG836).
 3. THE ACCURACY OF THIS SURVEY IS COMMENSURATE WITH THE DRAWING SCALE SPECIFIED WITHIN THE TITLE BLOCK. CHECK ALL CRUCIAL DIMENSIONS ON-SITE.
 4. SERVICES INCLUDING MANHOLES AND TELEGRAPH POSTS HAVE BEEN SURVEYED WHERE FOUND.
 5. WHILST EVERY EFFORT HAS BEEN MADE TO INCLUDE ALL ACCESSIBLE DETAIL, SOME FEATURES MAY NOT BE SHOWN IF OBSCURED AT THE TIME OF SURVEY (e.g. AREA OVERGROWN/STOCKPILES).
 6. PREVIOUS SURVEY INFORMATION SHOWN IN GREY TAKEN FROM DRAWING REFERENCE Topographical Survey Fishing Swims.dwg SUPPLIED BY SHEERNESS RECYCLING (HYTHE) LTD

- LEGEND
- PROPOSED MAJOR CONTOURS AT 500mm INTERVALS
 - PROPOSED MINOR CONTOURS AT 100mm INTERVALS
 - INDICATIVE VEHICLE ROUTE
 - PERMANENT WATER
 - PROPOSED HEADWALL


0	PS	IMR	3/24	FIRST ISSUE:
Revision	By	Chk'd By	Date	Comments
SHEERNESS RECYCLING LTD				
SLR global environmental solutions				
Site MARTELLO LAKES, HYTHE, KENT				
Project NICKHOLLS QUARRY REDEVELOPMENT				
Drawing Title PROPOSED LAYOUT VEHICLE MAINTENANCE ACCESS SOUTH - DETAIL SHEET				
Scale 1:100 @ A1			Date MARCH 2024	
Drawing Number 016				Revision 0




- NOTES
1. SURVEY CARRIED OUT BY SLR CONSULTING LTD 28-30th MAY 2019.
 2. TOPOGRAPHICAL SURVEY INFORMATION SHOWN ON THIS DRAWING IS BASED UPON THE ORDINANCE SURVEY NATIONAL GRID HEIGHT AND PLAN DATUM DERIVED BY G.P.S. (OSTN15,OSGB36).
 3. THE ACCURACY OF THIS SURVEY IS COMMENSURATE WITH THE DRAWING SCALE SPECIFIED WITHIN THE TITLE BLOCK. CHECK ALL CRUCIAL DIMENSIONS ON-SITE.
 4. SERVICES INCLUDING MANHOLES AND TELEGRAPH POSTS HAVE BEEN SURVEYED WHERE FOUND.
 5. WHILST EVERY EFFORT HAS BEEN MADE TO INCLUDE ALL ACCESSIBLE DETAIL, SOME FEATURES MAY NOT BE SHOWN IF OBSCURED AT THE TIME OF SURVEY (e.g. AREA OVERGROWN/STOCKPILES)
 6. PREVIOUS SURVEY INFORMATION SHOWN IN GREY TAKEN FROM DRAWING REFERENCE Topographical Survey Fishing Swims.dwg SUPPLIED BY SHEERNESS RECYCLING (HYTHE) LTD

- LEGEND
- PROPOSED MAJOR CONTOURS AT 500mm INTERVALS
 - PROPOSED MINOR CONTOURS AT 100mm INTERVALS
 - INDICATIVE VEHICLE ROUTE
 - PERMANENT WATER
 - PROPOSED HEADWALL
 - ALIGNMENT OF EXISTING FOOTPATH & FOOTBRIDGE

0	PS	IMR	3/24	FIRST ISSUE:
Revision	By	Chk'd By	Date	Comments
SHEERNESS RECYCLING LTD				
SLR global environmental solutions				
Site MARTELLO LAKES, HYTHE, KENT				
Project NICKHOLLS QUARRY REDEVELOPMENT				
Drawing Title PROPOSED LAYOUT BUND TO SUBSTATION AT 2.25m DETAIL SHEET				
Scale 1:100 @ A1			Date MARCH 2024	
Drawing Number 016				Revision 0





Appendix E SuDS Area design results

Surface Water Drainage Design (Condition 37 Report)

Martello Lakes site (Nickolls Quarry Redevelopment)

Camland Hythe Ltd

SLR Project No.: 425.064675.00001

26 March 2024

SLR Consulting Ltd		Page 1				
4/5 Lockside View Edinburgh Park Edinburgh, EH12 9DH	Hythe wetland area 425.10088.00001					
Date 31/01/2024	Designed by SLR					
File 240304_425_10088_00001_...	Checked by					
Innovyze	Network 2020.1.3					
<u>Time Area Diagram for Storm</u> <table><thead><tr><th>Time (mins)</th><th>Area (ha)</th></tr></thead><tbody><tr><td>0-4</td><td>0.000</td></tr></tbody></table> Total Area Contributing (ha) = 0.000 Total Pipe Volume (m³) = 4441.511			Time (mins)	Area (ha)	0-4	0.000
Time (mins)	Area (ha)					
0-4	0.000					
©1982-2020 Innovyze						

SLR Consulting Ltd		Page 2
4/5 Lockside View Edinburgh Park Edinburgh, EH12 9DH	Hythe wetland area 425.10088.00001	
Date 31/01/2024 File 240304_425_10088_00001_...	Designed by SLR Checked by	
Innovyze	Network 2020.1.3	

STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
1.000	20.000	0.090	222.2	0.000	5.00	0.0	0.600	\/	-1	Pipe/Conduit	
1.001	60.000	0.005	12000.0	0.000	0.00	0.0	0.600	\/	-8	Pipe/Conduit	
1.002	12.000	0.070	171.4	0.000	0.00	0.0	0.600	ooo	-7	Pipe/Conduit	
1.003	210.000	0.005	42000.0	0.000	0.00	0.0	0.600	\/	-2	Pipe/Conduit	
1.004	12.000	0.070	171.4	0.000	0.00	0.0	0.600	4o	-5	Pipe/Conduit	
1.005	35.000	0.005	7000.0	0.000	0.00	0.0	0.600	\/	-3	Pipe/Conduit	
1.006	20.000	0.200	100.0	0.000	0.00	0.0	0.600	\/	-4	Pipe/Conduit	
1.007	10.000	0.125	80.0	0.000	0.00	0.0	0.600	\/	-4	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL E (m)	I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.000	50.00	5.16	1.900	0.000	0.0	0.0	0.0	2.05	1721.4	0.0
1.001	50.00	7.69	1.710	0.000	0.0	0.0	0.0	0.40	3253.5	0.0
1.002	49.72	7.82	1.100	0.000	0.0	0.0	0.0	1.55	739.5	0.0
1.003	25.41	24.29	1.710	0.000	0.0	0.0	0.0	0.21	2595.4	0.0
1.004	25.32	24.42	1.100	0.000	0.0	0.0	0.0	1.55	985.9	0.0
1.005	24.64	25.48	1.705	0.000	0.0	0.0	0.0	0.55	19449.3	0.0
1.006	24.60	25.54	1.425	0.000	0.0	0.0	0.0	5.39	21606.0	0.0
1.007	24.58	25.57	1.225	0.000	0.0	0.0	0.0	6.03	24162.5	0.0

Conduit Sections for Storm

NOTE: Diameters less than 66 refer to section numbers of hydraulic conduits. These conduits are marked by the symbols:- [] box culvert, \/ open channel, oo dual pipe, ooo triple pipe, O egg.

Section numbers < 0 are taken from user conduit table

Section Number	Conduit Type	Major Dimn. (mm)	Minor Dimn. (mm)	Side Slope (Deg)	Corner Splay (mm)	4*Hyd Radius (m)	XSect Area (m ²)
-1	\/	1000	350	14.0		0.864	0.841
-2	\/	24900	450	11.3		1.657	12.218
-3	\/	76000	450	11.3		1.748	35.213
-4	\/	1000	1000	18.4		2.184	4.006
-5	4o	1800	450			0.450	0.636
-7	ooo	1350	450			0.450	0.477
-8	\/	16000	450	11.3		1.595	8.213

SLR Consulting Ltd		Page 3
4/5 Lockside View Edinburgh Park Edinburgh, EH12 9DH	Hythe wetland area 425.10088.00001	
Date 31/01/2024 File 240304_425_10088_00001_...	Designed by SLR Checked by	
Innovyze	Network 2020.1.3	

Manhole Schedules for Storm

MH Name	MH CL (m)	MH Depth (m)	MH Connection	MH Diam., L*W (mm)	PN	Pipe Out Invert Level (m)	Diameter (mm)	PN	Pipes In Invert Level (m)	Diameter (mm)	BA
Catchment C	2.350	0.450	Junction		1.000	1.900	-1				
FIRST BASIN	2.350	0.640	Junction		1.001	1.710	-8	1.000	1.810	-1	
PIPE CROSSING 1	2.350	1.250	Junction		1.002	1.100	-7	1.001	1.705	-8	
Catchment A	2.350	1.320	Junction		1.003	1.710	-2	1.002	1.030	-7	
PIPE CROSSING 2	2.350	1.250	Junction		1.004	1.100	-5	1.003	1.705	-2	
Catchment B	2.350	1.320	Junction		1.005	1.705	-3	1.004	1.030	-5	
POND	2.350	0.925	Junction		1.006	1.425	-4	1.005	1.700	-3	
Culvert	2.325	1.100	Junction		1.007	1.225	-4	1.006	1.225	-4	
Pond	2.250	1.150	Open Manhole	0		OUTFALL		1.007	1.100	-4	

No coordinates have been specified, layout information cannot be produced.

SLR Consulting Ltd		Page 4
4/5 Lockside View Edinburgh Park Edinburgh, EH12 9DH	Hythe wetland area 425.10088.00001	
Date 31/01/2024 File 240304_425_10088_00001_...	Designed by SLR Checked by	
Innovyze	Network 2020.1.3	

PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
1.000	\/	-1	Catchment C	2.350	1.900	0.100	Junction	
1.001	\/	-8	FIRST BASIN	2.350	1.710	0.190	Junction	
1.002	ooo	-7	PIPE CROSSING 1	2.350	1.100	0.800	Junction	
1.003	\/	-2	Catchment A	2.350	1.710	0.190	Junction	
1.004	4o	-5	PIPE CROSSING 2	2.350	1.100	0.800	Junction	
1.005	\/	-3	Catchment B	2.350	1.705	0.195	Junction	
1.006	\/	-4	POND	2.350	1.425	-0.075	Junction	
1.007	\/	-4	Culvert	2.325	1.225	0.100	Junction	

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
1.000	20.000	222.2	FIRST BASIN	2.350	1.810	0.190	Junction	
1.001	60.000	12000.0	PIPE CROSSING 1	2.350	1.705	0.195	Junction	
1.002	12.000	171.4	Catchment A	2.350	1.030	0.870	Junction	
1.003	210.000	42000.0	PIPE CROSSING 2	2.350	1.705	0.195	Junction	
1.004	12.000	171.4	Catchment B	2.350	1.030	0.870	Junction	
1.005	35.000	7000.0	POND	2.350	1.700	0.200	Junction	
1.006	20.000	100.0	Culvert	2.325	1.225	0.100	Junction	
1.007	10.000	80.0	Pond	2.250	1.100	0.150	Open Manhole	0

SLR Consulting Ltd		Page 5
4/5 Lockside View Edinburgh Park Edinburgh, EH12 9DH	Hythe wetland area 425.10088.00001	
Date 31/01/2024 File 240304_425_10088_00001_...	Designed by SLR Checked by	
Innovyze	Network 2020.1.3	

Area Summary for Storm

Pipe Number	PIMP Type	PIMP Name	PIMP (%)	Gross Area (ha)	Imp. Area (ha)	Pipe Total (ha)
1.000	-	-	100	0.000	0.000	0.000
1.001	-	-	100	0.000	0.000	0.000
1.002	-	-	100	0.000	0.000	0.000
1.003	-	-	100	0.000	0.000	0.000
1.004	-	-	100	0.000	0.000	0.000
1.005	-	-	100	0.000	0.000	0.000
1.006	-	-	100	0.000	0.000	0.000
1.007	-	-	100	0.000	0.000	0.000
				Total	Total	Total
				0.000	0.000	0.000

SLR Consulting Ltd		Page 6
4/5 Lockside View Edinburgh Park Edinburgh, EH12 9DH	Hythe wetland area 425.10088.00001	
Date 31/01/2024 File 240304_425_10088_00001_...	Designed by SLR Checked by	
Innovyze	Network 2020.1.3	

Online Controls for Storm

Depth/Flow Relationship Manhole: POND, DS/PN: 1.006, Volume (m³): 1232.5

Invert Level (m) 1.700

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.010	51.1000	0.090	1379.9000	0.170	3582.2000	0.250	6388.4000
0.020	144.6000	0.100	1616.1000	0.180	3902.9000	0.260	6775.5000
0.030	265.6000	0.110	1864.5000	0.190	4232.6000	0.270	7170.1000
0.040	408.9000	0.120	2124.5000	0.200	4571.1000	0.280	7572.1000
0.050	571.4000	0.130	2395.5000	0.210	4918.2000	0.290	7981.4000
0.060	751.1000	0.140	2677.1000	0.220	5273.7000	0.300	8397.7000
0.070	946.5000	0.150	2969.0000	0.230	5637.3000		
0.080	1156.4000	0.160	3270.8000	0.240	6008.9000		

SLR Consulting Ltd		Page 7
4/5 Lockside View Edinburgh Park Edinburgh, EH12 9DH	Hythe wetland area 425.10088.00001	
Date 31/01/2024 File 240304_425_10088_00001_...	Designed by SLR Checked by	
Innovyze	Network 2020.1.3	
<u>Offline Controls for Storm</u> <u>Weir Manhole: PIPE CROSSING 2, DS/PN: 1.004, Loop to PN: 1.005</u> Discharge Coef 0.544 Width (m) 35.000 Invert Level (m) 1.935		
©1982-2020 Innovyze		

SLR Consulting Ltd		Page 8
4/5 Lockside View Edinburgh Park Edinburgh, EH12 9DH	Hythe wetland area 425.10088.00001	
Date 31/01/2024 File 240304_425_10088_00001_...	Designed by SLR Checked by	
Innovyze	Network 2020.1.3	

Storage Structures for Storm

Tank or Pond Manhole: Culvert, DS/PN: 1.007

Invert Level (m) 1.225

Depth (m)	Area (m ²)	Depth (m)	Area (m ²)
0.000	200.0	1.100	420.0

Time Area Diagram at Pipe Number 1.000 for Storm

Total Area (ha) 0.259

Time (mins)	Area	Time (mins)	Area
From: To: (ha)		From: To: (ha)	
0 4	0.130	4 8	0.129

Time Area Diagram at Pipe Number 1.003 for Storm

Total Area (ha) 15.551

Time (mins)	Area	Time (mins)	Area	Time (mins)	Area	Time (mins)	Area
From: To: (ha)		From: To: (ha)		From: To: (ha)		From: To: (ha)	
0 4	1.556	12 16	1.555	24 28	1.555	36 40	1.555
4 8	1.555	16 20	1.555	28 32	1.555		
8 12	1.555	20 24	1.555	32 36	1.555		

Time Area Diagram at Pipe Number 1.005 for Storm

Total Area (ha) 8.451

Time (mins)	Area	Time (mins)	Area	Time (mins)	Area	Time (mins)	Area
From: To: (ha)		From: To: (ha)		From: To: (ha)		From: To: (ha)	
0 4	1.057	8 12	1.057	16 20	1.056	24 28	1.056
4 8	1.057	12 16	1.056	20 24	1.056	28 32	1.056

SLR Consulting Ltd

Page 9

4/5 Lockside View

Edinburgh Park

Edinburgh, EH12 9DH

Hythe wetland area

425.10088.00001

Date 31/01/2024

Designed by SLR

File 240304_425_10088_00001_...

Checked by

Innovyze

Network 2020.1.3

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)

for Storm

Simulation Criteria

Areal Reduction Factor 1.000

Additional Flow - % of Total Flow 0.000

Hot Start (mins) 0

MADD Factor * 10m³/ha Storage 2.000

Hot Start Level (mm) 0

Inlet Coefficient 0.800

Manhole Headloss Coeff (Global) 0.500

Flow per Person per Day (l/per/day) 0.000

Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0

Number of Storage Structures 1

Number of Online Controls 1

Number of Time/Area Diagrams 3

Number of Offline Controls 1

Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model

FEH

FEH Rainfall Version

2013

Site Location GB 612750 133400 TR 12750 33400

Data Type

Catchment

Cv (Summer)

0.750

Cv (Winter)

0.840

Margin for Flood Risk Warning (mm) 300.0

DVD Status OFF

Analysis Timestep

Fine Inertia Status OFF

DTS Status

ON

Profile(s)

Summer and Winter

Duration(s) (mins)

15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080

Return Period(s) (years)

2, 30, 100

Climate Change (%)

0, 0, 40

PN

US/MH Name

Storm

Return Period

Climate Change

First (X) Surge

First (Y) Flood

First (Z) Overflow

1.000

Catchment C

15 Winter

2

+0%

1.001

FIRST BASIN

120 Winter

2

+0%

1.002

PIPE CROSSING 1

120 Winter

2

+0%

2/15 Summer

1.003

Catchment A

120 Winter

2

+0%

1.004

PIPE CROSSING 2

120 Winter

2

+0%

2/15 Summer

30/30 Summer

1.005

Catchment B

120 Winter

2

+0%

1.006

POND

120 Winter

2

+0%

1.007

Culvert

120 Winter

2

+0%

PN

US/MH Name

Overflow Act.

Water Level (m)

Surcharged Depth (m)

Flooded Volume (m³)

Half Drain Time (mins)

Pipe Flow (l/s)

1.000

Catchment C

1.940

-0.310

0.000

0.03

1.001

FIRST BASIN

1.836

-0.324

0.000

0.00

©1982-2020 Innovyze

SLR Consulting Ltd		Page 10
4/5 Lockside View Edinburgh Park Edinburgh, EH12 9DH	Hythe wetland area 425.10088.00001	
Date 31/01/2024 File 240304_425_10088_00001_...	Designed by SLR Checked by	
Innovyze	Network 2020.1.3	

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Overflow Act.	Water Surcharged Flooded			Flow / Cap.	Overflow (l/s)	Half Drain Pipe	
			Level (m)	Depth (m)	Volume (m³)			Time (mins)	Flow (l/s)
1.002	PIPE CROSSING 1		1.836	0.286	0.000	0.08			38.3
1.003	Catchment A		1.836	-0.324	0.000	0.04			667.7
1.004	PIPE CROSSING 2	29	1.816	0.266	0.000	0.96	0.0		651.7
1.005	Catchment B		1.782	-0.373	0.000	0.02			975.0
1.006	POND		1.771	-0.654	0.000	0.10			971.9
1.007	Culvert		1.425	-0.800	0.000	0.10			973.1

PN	US/MH Name	Status	Level Exceeded
1.000	Catchment C	OK	
1.001	FIRST BASIN	OK	
1.002	PIPE CROSSING 1	SURCHARGED*	
1.003	Catchment A	OK	
1.004	PIPE CROSSING 2	SURCHARGED*	
1.005	Catchment B	OK	
1.006	POND	OK	
1.007	Culvert	OK	

SLR Consulting Ltd

4/5 Lockside View
Edinburgh Park
Edinburgh, EH12 9DH

Date 31/01/2024
File 240304_425_10088_00001_...

Innovyze

Hythe wetland area

425.10088.00001

Designed by SLR

Checked by

Network 2020.1.3

Page 11



30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)

for Storm

Simulation Criteria

Areal Reduction Factor 1.000

Additional Flow - % of Total Flow 0.000

Hot Start (mins) 0

MADD Factor * 10m³/ha Storage 2.000

Hot Start Level (mm) 0

Inlet Coefficient 0.800

Manhole Headloss Coeff (Global) 0.500

Flow per Person per Day (l/per/day) 0.000

Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0

Number of Storage Structures 1

Number of Online Controls 1

Number of Time/Area Diagrams 3

Number of Offline Controls 1

Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FEH

FEH Rainfall Version 2013

Site Location GB 612750 133400 TR 12750 33400

Data Type Catchment

Cv (Summer) 0.750

Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0

DVD Status OFF

Analysis Timestep Fine Inertia Status OFF

DTS Status ON

Profile(s) Summer and Winter

Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080

Return Period(s) (years) 2, 30, 100

Climate Change (%) 0, 0, 40

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow
1.000	Catchment C	60 Winter	30	+0%			
1.001	FIRST BASIN	60 Winter	30	+0%			
1.002	PIPE CROSSING 1	60 Winter	30	+0%	2/15 Summer		
1.003	Catchment A	60 Winter	30	+0%			
1.004	PIPE CROSSING 2	60 Winter	30	+0%	2/15 Summer		30/30 Summer
1.005	Catchment B	60 Winter	30	+0%			
1.006	POND	60 Winter	30	+0%			
1.007	Culvert	60 Winter	30	+0%			

PN	US/MH Name	Overflow Act.	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Half Drain Flow / Cap. (l/s)	Time (mins)
1.000	Catchment C		1.991	-0.259	0.000	0.04	
1.001	FIRST BASIN		1.991	-0.169	0.000	0.00	

©1982-2020

Innovyze

SLR Consulting Ltd		Page 12
4/5 Lockside View Edinburgh Park Edinburgh, EH12 9DH	Hythe wetland area 425.10088.00001	
Date 31/01/2024 File 240304_425_10088_00001_...	Designed by SLR Checked by	
Innovyze	Network 2020.1.3	

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Overflow Act.	Water	Surcharged	Flooded	Flow / Cap.	Overflow (l/s)	Half Drain Time (mins)
			Level (m)	Depth (m)	Volume (m³)			
1.002	PIPE CROSSING 1		1.991	0.441	0.000	0.21		
1.003	Catchment A		1.992	-0.168	0.000	0.08		
1.004	PIPE CROSSING 2	29	1.982	0.432	0.000	1.39	290.2	
1.005	Catchment B		1.816	-0.339	0.000	0.04		
1.006	POND		1.805	-0.620	0.000	0.19		
1.007	Culvert		1.513	-0.712	0.000	0.19		

PN	US/MH Name	Pipe Flow (l/s)	Status	Level Exceeded
1.000	Catchment C	45.6	OK	
1.001	FIRST BASIN	43.3	OK	
1.002	PIPE CROSSING 1	105.2	SURCHARGED*	
1.003	Catchment A	1415.7	OK	
1.004	PIPE CROSSING 2	936.9	SURCHARGED*	
1.005	Catchment B	1742.0	OK	
1.006	POND	1738.2	OK	
1.007	Culvert	1737.7	OK	

SLR Consulting Ltd		Page 14
4/5 Lockside View Edinburgh Park Edinburgh, EH12 9DH	Hythe wetland area 425.10088.00001	
Date 31/01/2024 File 240304_425_10088_00001_...	Designed by SLR Checked by	
Innovyze	Network 2020.1.3	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Overflow Act.	Water	Surcharged	Flooded	Flow / Cap.	Overflow (l/s)	Half Drain Time (mins)
			Level (m)	Depth (m)	Volume (m³)			
1.002	PIPE CROSSING 1		2.052	0.502	0.000	0.21		
1.003	Catchment A		2.051	-0.109	0.000	0.16		
1.004	PIPE CROSSING 2	29	2.035	0.485	0.000	1.39	1887.4	
1.005	Catchment B		1.900	-0.255	0.000	0.10		
1.006	POND		1.890	-0.535	0.000	0.45		
1.007	Culvert		1.669	-0.556	0.000	0.45		

PN	US/MH Name	Pipe Flow (l/s)	Status	Level Exceeded
1.000	Catchment C	83.0	FLOOD RISK*	
1.001	FIRST BASIN	79.7	FLOOD RISK*	
1.002	PIPE CROSSING 1	105.2	FLOOD RISK*	
1.003	Catchment A	2731.8	FLOOD RISK*	
1.004	PIPE CROSSING 2	941.7	SURCHARGED*	
1.005	Catchment B	4254.3	OK	
1.006	POND	4237.4	OK	
1.007	Culvert	4237.7	OK	

SLR Consulting Ltd

Page 1

4/5 Lockside View

Edinburgh Park

Edinburgh, EH12 9DH

Hythe wetland area

425.10088.00001

Date 31/01/2024

File 240304_425_10088_00001_...

Designed by SLR

Checked by

Innovyze

Network 2020.1.3

Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000

Additional Flow - % of Total Flow 0.000

Hot Start (mins) 0

MADD Factor * 10m³/ha Storage 2.000

Hot Start Level (mm) 0

Inlet Coefficient 0.800

Manhole Headloss Coeff (Global) 0.500

Flow per Person per Day (l/per/day) 0.000

Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0

Number of Storage Structures 1

Number of Online Controls 1

Number of Time/Area Diagrams 3

Number of Offline Controls 1

Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FEH

FEH Rainfall Version 2013

Site Location GB 612750 133400 TR 12750 33400

Data Type Catchment

Cv (Summer) 0.750

Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0

DVD Status OFF

Analysis Timestep Fine

Inertia Status OFF

DTS Status ON

Profile(s) Summer and Winter

Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080

Return Period(s) (years) 2, 30, 100

Climate Change (%) 0, 0, 60

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow
1.000	Catchment C	60 Winter	100	+60%			
1.001	FIRST BASIN	60 Winter	100	+60%			
1.002	PIPE CROSSING 1	60 Winter	100	+60%	2/15 Summer		
1.003	Catchment A	60 Winter	100	+60%			
1.004	PIPE CROSSING 2	60 Winter	100	+60%	2/15 Summer		30/30 Summer
1.005	Catchment B	60 Winter	100	+60%			
1.006	POND	60 Winter	100	+60%			
1.007	Culvert	60 Winter	100	+60%			

PN	US/MH Name	Overflow Act.	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Cap.	Overflow (l/s)	Half Drain Time (mins)
1.000	Catchment C		2.071	-0.179	0.000	0.08		
1.001	FIRST BASIN		2.070	-0.090	0.000	0.01		
1.002	PIPE CROSSING 1		2.068	0.518	0.000	0.21		

©1982-2020


Innovyze

SLR Consulting Ltd		Page 2
4/5 Lockside View Edinburgh Park Edinburgh, EH12 9DH	Hythe wetland area 425.10088.00001	
Date 31/01/2024 File 240304_425_10088_00001_...	Designed by SLR Checked by	
Innovyze	Network 2020.1.3	

Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Overflow Act.	Water	Surcharged	Flooded	Flow / Cap.	Overflow (l/s)	Half Drain Time (mins)
			Level (m)	Depth (m)	Volume (m³)			
1.003	Catchment A		2.067	-0.093	0.000	0.18		
1.004	PIPE CROSSING 2	30	2.049	0.499	0.000	1.39	2302.1	
1.005	Catchment B		1.922	-0.233	0.000	0.11		
1.006	POND		1.913	-0.512	0.000	0.51		
1.007	Culvert		1.702	-0.523	0.000	0.51		

PN	US/MH Name	Pipe Flow (l/s)	Status	Level Exceeded
1.000	Catchment C	94.6	FLOOD RISK*	
1.001	FIRST BASIN	90.8	FLOOD RISK*	
1.002	PIPE CROSSING 1	105.2	FLOOD RISK*	
1.003	Catchment A	3135.0	FLOOD RISK*	
1.004	PIPE CROSSING 2	941.1	SURCHARGED*	
1.005	Catchment B	4872.0	OK	
1.006	POND	4824.4	OK	
1.007	Culvert	4823.1	OK	



Appendix F Landscape Drawings


Surface Water Drainage Design (Condition 37 Report)

Martello Lakes site (Nickolls Quarry Redevelopment)

Camland Hythe Ltd

SLR Project No.: 425.064675.00001

26 March 2024



LOCATION PLAN - SCALE 1:5000

END OF LANDSCAPE WORKS

EXISTING GROUP VEGETATION
TO BE CUT BACK TO ACCOMMODATE
PROW AND SUDs

Refer to Drawing: 19182-WIE-ZZ-XX-DR-L-74102

KEY

- PROPOSED HEADWALLS TO THE ATTENUATION AREAS
- BOARD WALK AND VIEWING PLATFORMS
- 1.2m TIMBER POST AND RAIL FENCING
- INDICATIVE LOCATION OF TIMBER BOARD WALK
- INDICATIVE SLOPE OF BOARD WALK
- TIMBER EDGING
- KNEE RAIL
- INDICATIVE LOCATION OF PH3 AND PH4 STREET LIGHTING FINAL LOCATIONS TO BE CONFIRMED AT A LATER STAGE
- REFER TO ARBORICULTURAL REPORT FOR DETAILS ON TREES TO BE REMOVED AND RETAINED
- EXISTING VEGETATION GROUP (RPA's shown in purple)
- EXISTING VEGETATION TO BE REMOVED
- INDICATIVE LEVEL OF BOARD WALK
- GRAVEL PATH

- SOFT LANDSCAPE
- EXISTING GRASSLAND TO BE RETAINED
Any gaps in grassland to be made good by sowing with EM2 by Emorsgate or equivalent approved
- PROPOSED AMENITY GRASS
EG22 by Emorsgate or equivalent approved
- PROPOSED WILDFLOWER MEADOW MIX
EM2 by Emorsgate or equivalent approved
- PROPOSED WILDFLOWER MEADOW MIX FOR WETLANDS
EM8 by Emorsgate or equivalent approved
- PROPOSED TUSsock GRASSLAND
EM10 by Emorsgate or equivalent approved
- PROPOSED MOWN PATH THROUGH GRASSLAND OR WILDFLOWER MEADOW
- PROPOSED REED BEDS
- PROPOSED MARGINAL PLANTING
Refer to planting schedule for details
- PROPOSED AQUATIC PLANTING
Refer to planting schedule for details
- PROPOSED NATIVE SUB-CANOPY PLANTING
Refer to planting schedule for details
- PROPOSED NATIVE BUFFER PLANTING
Refer to planting schedule for details
- PROPOSED SHINGLE PLANTING
Refer to planting schedule for details
- PROPOSED TREE
Refer to planting schedule for details

P03	30.10.23	TUSsock GRASSLAND ADDED	KK	TH
P02	03.08.23	BOARDWALK AND VIEWING PLATFORM AMENDED	KK	TH
P01	12.07.23	FIRST ISSUE	KK	TH
Rev	Date	Description	By	Chk

Amendments

Project

Martello Lakes - Northern POS

Title

GENERAL ARRANGEMENT
LANDSCAPE PLAN
SHEET 1 OF 6

Client

CAMLAND - HYTHE LTD

w waterman

Merchants House Wapping Road Bristol BS1 4RW
t 0117 937 8200
mail@watermangroup.com www.watermangroup.com

Suitability

INFORMATION

Designed By

Director

Waterman Ref



Drawn By

Date

Project

19182-WIE-ZZ-XX-DR-L-74101

P03



END OF LANDSCAPE WORKS